WATER-SUPPLY AND STORES DIVISION.

Dated 6th October 1909.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Water-Supply and Stores Division, up to 1st November 1909, for constructing four balancing tanks and Superintendent's quarters at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1910.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory notes as earnest money and be superscribed "Tender for four balancing tanks and Superintendent's quarters," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Approximate estimate of quantities of works to be done in the town of Shimoga.

Items of work	Per	Quantities			Total quantity
		Constructing three balancing tanks	Constructing one balancing tank	Constructing Superintendent's quarters	
Earthwork, excavation	C. yd.	195	33	...	228
Concrete in surki mortar	C. ft.	6,060	978	...	7,038
Burnt brick in surki mortar	Do	9,174	1,998	...	11,174
Plastering with ½" thick cement	Sqr.	45·21	8·11	...	53·32
Do surki mortar	Do	71·55	13·72	...	85·27
Stone pillars 6" roughly dressed	S. ft.	99	8	...	107
Stone girders 8" do	Do	264	26	...	290
Covering slab 4" thick dressed on edge	Do	3,636	637	...	4,273
Teakwood ventilator with perforated zinc sheet, complete	Do	162	36	...	198
Manhole shutter with teakwood frame	No.	3	1	..	4
Iron ladder	Do	3	1	...	4
Cornice work including plastering	R. ft.	381	85	...	470
Pointing for ceiling of covering slab	Sqr.	2,892	396	...	3,288
Stone in mortar	C. ft.	...	...	922	922
Burnt brick in clay	Do	...	...	1,005	1,005
Do in chunam	Do	...	...	418	418
Burnt stone slabs, 6" thick, ordinary	S. ft.	...	...	109	109
Cutting grooves on top of pillars	No.	...	...	2	2
Coping with burnt brick in chunam and chunam plastering	R. ft.	...	...	70	70
Plastering with mud	Sqr.	...	...	14·53	14·53
Plastering with chunam	Do	...	...	16·04	16·04
Whitewashing	Do	...	...	14·53	14·53
Color-washing	Do	...	...	16·04	16·04
Cuddappa slab flooring over 3" sand bed with cement pointing.	Do	...	...	1·20	1·20
Flooring with Basel Mission square tiles over 3" concrete bed with cement pointing.	Do	...	...	2·09	·00
Roofing with 1st class Mangalore tiles with teak reepers, chunam borders.	Do	...	...	7·69	7·69
Teakwood work with wood oiling	C. ft.	...	...	48·43	48·43
Teakwood doors, battened	S. ft.	...	...	104	104
Teakwood windows with iron bars and pannelled shutters	Do	...	...	72	72
Chocolate painting	Sqr.	...	...	2·88	2·88
Teakwood eave boards, complete	S. ft.	...	...	46	46
Do finials, large	No.	...	...	2	2
Do do small	Do	...	...	6	6
Filling with earth watering and tamping	C. yds.	...	...	11	11

V. RANGASWAMI IYENGAR,